

Hindringham 2008

Insurance Repair Circa £36,000 competitive tender

Under-pin house beside the stream then demolish and re install retaining wall damaged by flash flooding



Flash flooding rose over the retaining wall and patio area causing the retaining wall to fail



GTRP installed under-pinning to the bungalow to a depth below the adjacent stream bed level (note under-pinning evident in the picture). The stream was then diverted through pipe work but if flash flooding occurred the excess water is allowed to run through the concrete foundation works area



13 inch block work wall with weep holes installed



Stream back flowing down the original line